



**Atkore-Heritage Plastics
AWWA C900 Pressure Pipe**



16100 South Lathrop Avenue
Harvey, IL 60426

Office 708-339-1610

Phone 800-882-5543

Web atkore.com

Date: **August 8, 2025**

Subject: Request for formal review of AWWA C900 Pressure Pipe

Dear Members of the Product Review Committee,

On behalf of Atkore International, Inc., I respectfully submit our AWWA C900 Pressure Pipe products for your evaluation and consideration for inclusion on the County Approved Product List (APL). Atkore, headquartered at 16100 South Lathrop Avenue in Harvey, Illinois, has delivered best-in-class infrastructure piping solutions for over a decade. Our manufacturing facilities provide dedicated capacity and technical expertise in both PVC and HDPE Pipe production.

Enclosed you will find our full project submittal, including technical specifications, performance data, and evidence of third-party testing. We trust that this documentation demonstrates both our product quality and our commitment to responsive service, from engineering support through on-time delivery and installation guidance.

We kindly request that deciding party review our submittal at your earliest convenience and approve Atkore's pipe products for your APL. Should you have any questions or require additional information, please contact me directly at (773)558-1785 or email kszacilowski@atkore.com.

Thank you for your consideration. We look forward to the opportunity to support your water transmission and infrastructure projects!

Best Regards,

Karol Szacilowski

Product Manager, HDPE and PVC

Atkore Plastic Pipe and Conduit

Mobile 773 558 1785

Email kszacilowski@atkore.com

James Gilchrist, PE

Director of Engineering

Atkore Plastic Pipe and Conduit

Direct 682 348 0496

Mobile 501 658 6431

Email jgilchrist@atkore.com



16100 South Lathrop Avenue
Harvey, IL 60426

Office 708-339-1610
Phone 800-882-5543
Web atkore.com

February 20, 2025

History of Pipe Manufacturing:

Atkore has a long history in the manufacture of high-quality plastic pipe solutions. Pipe for the water markets has been manufactured under the Heritage Plastics brand since the 1990s and the United Poly Systems brand since 2012. Atkore acquired these companies in 2013 and 2022, respectively, strengthening its commitment to delivering superior piping solutions.

United Poly Systems, LLC was established in 2011 to produce High-Density Polyethylene (HDPE) pipe; with over 40 years of combined industry experience. Starting with two production lines in 2011, United Poly Systems expanded to four lines by 2013. In 2015, a second state-of-the-art manufacturing facility was opened in Albuquerque, NM. Over the next four years, four additional production lines were added between the two plants. In its first decade, the company produced over 120,000 miles of pipe.

In June 2022, Atkore, Inc. acquired United Poly Systems. Based in Harvey, IL, Atkore is a leading provider of electrical, safety, and infrastructure solutions. The acquisition strengthens Atkore's product portfolio, expands manufacturing capacity, and further enables the company to meet HDPE customers' needs.

Key Milestones in Pipe Manufacturing:

- 1992 – Introduction of 2729 & 3034 BE/GB pipe (PVC)
- 1998 – Expansion to Sch40/Sch80 & IPS Class Pipe (PVC)
- 2011 – Founding of United Poly Systems, launch of HDPE pipe production
- 2013 – Expansion to four production lines (HDPE)
- 2015 – Opening of Albuquerque, NM manufacturing facility
- 2019 – Additional production lines added, surpassing 120,000 miles of pipe produced
- 2022 – Launch of Cell Core technology (PVC)

These advancements reflect our ongoing commitment to innovation and excellence in plastic pipe manufacturing.

Best Regards,

Karol Szacilowski

Product Manager, HDPE and PVC

Atkore Plastic Pipe and Conduit

Mobile 708 603 5568

Email kszacilowski@atkore.com

James Gilchrist, PE

Director of Engineering

Atkore Plastic Pipe and Conduit

Direct 682 348 0496

Mobile 501 658 6431

Email jgilchrist@atkore.com

PVC AWWA C900 PRESSURE PIPE

POTABLE WATER, RECLAIMED
WATER, AND SEWER APPLICATIONS



C900 is the long-lasting, reliable choice for municipal water systems. It's corrosion resistant and sustains water quality over the course of its long lifetime. These benefits, along with cost effectiveness and ease of installation, have made C900 the preferred pipe for waterworks projects, including potable water, reclaimed water, and sewer applications.

Specifications

- **Pipe Standards:** AWWA C900, UL1285, and FM1612
- **Diameter Standard:** Cast-Iron (CI)
- **Trade Sizes:** 4", 6", 8", 10", and 12"
- **Pressure Classes:** DR 25 – 165 psi, DR 18 – 235 psi, and DR 14 – 305 psi Note: FM Pressure rating is 250 psi for DR 14 and 185 psi for DR 18.
- **Lay Length:** 20'
- **Pipe Compound:** ASTM D1784, Cell Class 12454
- **Pipe Joint Standard:** ASTM D3139
- **Max Angular Joint Deflection:** 1°
- **Gasket Standard:** ASTM F477
- **Gasket Material Offering:** SBR
- **Installation Standard:** Atkore Installation Guide
- **Colors:** Blue (standard), Green and Purple (available upon request)
- **Certifications:** NSF14, FM1612



Scan to view
installation instructions.



Product Data

Trade Size	Part Number	Dimensions (in)							Approx. Weight per Foot (lbs)	Crate Quantity (ft)
		OD	ID	D	BOD	T	E1	E2		
DR 25 - Pressure Rating 165 psi										
4	3640020G	4.80	4.40	5.50	6.02	0.192	4.38	5.38	1.898	960
6	3660020G	6.90	6.32	6.25	8.39	0.276	5.00	6.00	3.931	280
8	3680020G	9.05	8.29	7.50	10.86	0.362	6.25	7.25	6.800	200
10	36100020G	11.10	10.17	8.75	13.28	0.444	7.50	8.50	10.291	160
12	36120020G	13.20	12.09	9.25	15.63	0.528	8.00	9.00	14.583	60
DR 18 - Pressure Rating 235 psi*										
4	3740020G	4.80	4.24	5.50	6.17	0.267	4.38	5.38	2.594	960
6	3760020G	6.90	6.10	6.25	8.62	0.383	5.00	6.00	5.376	280
8	3780020G	9.05	7.99	7.50	11.16	0.503	6.25	7.25	9.309	200
10	37100020G	11.10	9.81	8.75	13.66	0.617	7.50	8.50	14.095	160
12	37120020G	13.20	11.66	9.25	16.10	0.733	8.00	9.00	19.988	60
DR 14 - Pressure Rating 305 psi*										
4	3840020G	4.80	4.08	5.50	6.34	0.343	4.38	5.38	3.282	960
6	3860020G	6.90	5.87	6.25	8.88	0.493	5.00	6.00	6.809	280
8	3880020G	9.05	7.69	7.50	11.51	0.646	6.25	7.25	11.798	200
10	38100020G	11.10	9.44	8.75	14.09	0.793	7.50	8.50	17.876	160
12	38120020G	13.20	11.22	9.25	16.61	0.943	8.00	9.00	25.357	60

Note: FM pressure rating is 250 psi for DR 14 and 185 psi for DR 18.
All dimensions are subject to normal manufacturing tolerances.




Illustration Legend

Code	Description	Code	Description
OD	Average OD (in)	T	Minimum Wall Thickness (in)
ID	Approx. Internal Diameter (in)	E1	Nominal Distance Between First Insertion Line to End of Spigot (in)
D	Nominal Bell Depth (in)	E2	Nominal Distance Between Second Insertion Line to End of Spigot (in)
BOD	Approx. Bell Outside Diameter (in)		





PVC AWWA C900 Pressure Pipe

The tough and reliable solution
for municipal water systems



Atkore[™]
Heritage
Plastics

Atkore (NYSE: ATKR) is a global manufacturer of industrial products with +5,000 employees and 50 manufacturing and distribution plants producing a wide range of PVC and HDPE pipe products for Municipal/Waterworks, Plumbing, Irrigation, Industrial and Electrical applications.

Why Choose Heritage Plastics?

With our expanded product offerings, large network of manufacturing locations, and relentless focus on our customers, Heritage Plastics by Atkore provides an end-to-end solution for water infrastructure projects.


PVC

- AWWA C900
- ASTM D 3034 Solvent Weld and Gasketed Sewer
- ASTM D 2241 Solvent Weld and Gasketed Pressure
- ASTM D 1785 Schedule 40/80 Pressure
- ASTM F 891 DWV Cellular Core

HDPE

- ASTM F 714 DIPS & IPS
- ASTM D 3035 IPS
- ASTM D 2737 CTS Water Tubing
- ASTM D 2513 MDPE & HDPE Gas
- ASTM F 2619 Oil & Gas

PVC & HDPE Plant Locations



- 1 Eugene, OR
- 2 Pendleton, OR
- 3 Albuquerque, NM
- 4 Dallas, TX
- 5 Springfield, MO
- 6 Louisville, KY
- 7 Tampa, FL



Product Description

C900 is the most common PVC pressure pipe product utilized in municipal water pipe systems. Standard laying lengths are 20 feet and the pipe is typically blue in color to signify potable water. C900 is manufactured with one integral gasketed bell per length. Dual insertion lines, on the spigot end, facilitate proper assembly.

Material

The PVC compound meets ASTM D 1784, cell class 12454.

Pipe

The pipe meets AWWA C900 and FM 1612 with pressure ratings below.

DR	Pressure Rating (psi)	
	AWWA C900	FM 1612
25	165	Factory Mutual does not apply to DR 25 products
18	235	185
14	305	250

Corrosion Resistance

C900 is immune to nearly all types of internal and external corrosion. As a non-conductor, PVC is not impacted by electrolysis or susceptible to degradation from alkaline or acidic soil conditions. No additional bagging or cathodic protection is required. A correctly installed Heritage Plastics system will provide long-term service at reduced operating costs.

Water Quality

Unlike other materials, PVC is proven to sustain water quality over time and eliminate potential contamination resulting from pipeline degradation. Extractant water purity tests, performed by independent test laboratories, ensure that our pipe meets the requirements for drinking water as specified by NSF Standard 61.

Elastomeric Seal

Pipe is provided with factory-installed gaskets which meet ASTM F 477.

Gasketed Joint Assembly

Joints meet requirements of ASTM D 3139.

Installation

Refer to AWWA M23 PVC Pipe - Design and Installation manual and AWWA C605 Underground Installation of Polyvinyl Chloride (PVC) Pressure Pipe and Fittings.



Exceptional Strength and Durability

C900 has demonstrated high performance in all weather conditions and climates across the U.S. for water mains, sanitary sewer force mains, and fire lines. **Every piece of C900 is hydrostatically proof tested (see table on page 5).** The ability of PVC to bend without breaking allows the joint and pipe assembly to compensate for minor earth movements, which may cause problems in more rigid, non-PVC assemblies.

Superior Flow Characteristics

Due to its extremely smooth inner surface, C900 has a Hazen-Williams flow coefficient of $C=150$, or better. This reduces friction between pipe walls and water moving through the pipe, resulting in a lower burden on pumps and reduced pumping costs. C900 also resists tuberculation throughout its long lifespan.

Joint Integrity

The integral bell gasketed joint meets the same strength requirements of the C900 pipe, as well as the test criteria of ASTM D 3139.

Certification


C900 is tested to maintain listings from NSF and Factory Mutual (FM). Factory Mutual does not apply to DR 25 products.



Basic Assembly Instructions



Step 1: Clean all debris from the bell end of the pipe. Check the gasket position. Be sure it's completely seated in the groove, with no raised areas.



Step 2: Lubricate the gasket ID and spigot end using the Heritage Plastics recommended lubricant supplied with the pipe.



Step 3: Place the pipes in straight alignment. Push the spigot end into the bell past the first insertion line but no further than the second.

The Basic Assembly Instructions are not intended as a substitution for full instructions. Refer to AWWA M23 - PVC Pipe Design and Installation manual and AWWA C605 for Underground Installation of Polyvinyl Chloride (PVC) Pressure Pipe and Fittings for full instructions.

Pipe Embedment

All PVC pipe should be installed with bedding that provides uniform longitudinal support. Use embedment material that is free of large stones, frozen matter, or other debris. Use proper compaction procedures to provide soil densities as specified by the design engineer.

Quality Testing

Hydrostatic Proof Testing

Each piece of C900, including the integral bell, is tested to the indicated pressure level for a minimum of five seconds.

Quick Burst Test

Randomly selected C900 samples are tested in accordance with ASTM D 1599 to withstand pressures listed in the table below.

DR	Test Pressure (psi)	
	Hydrostatic Proof	Burst
25	330	535
18	582	755
14	800	985



Factors Affecting Design

Hydraulics

C900's pipe wall is extremely smooth and energy-efficient. It has a Hazen-Williams coefficient of C=150, or better.

Pressure Rating

Heritage Plastics offers a choice of three pressure ratings (refer to table on page 3). When you have questions or encounter unusual circumstances, call your Sales Representative.

Temperature

For operation at temperatures 80°F or higher, multiply the pressure class by these derating factors.

Temperature (°F)	Derating Factor
80°	0.88
90°	0.75
100°	0.62
110°	0.50
120°	0.40
140°	0.22

Axial Deflection

The joint is designed to allow for axial deflection of no more than 1 degree.

Longitudinal Bending

Axial deflection at the pipe joint in combination with longitudinal bending is not recommended; however, it is possible to curve C900 to allow for slight changes in direction. Bending to the below minimum radii will not jeopardize C900's design capabilities.

Trade Size	Minimum Bending Radius (ft)
4	100
6	144
8	189
10	231
12	275




Scan to view our Technical Bulletin "Longitudinal Bending of PVC Pipe" for more details.

WARNINGS: Do not use PVC pipe for pressurized air systems. Injury or death may result due to the catastrophic nature of pipe failure should failure occur. Rapid expansion of compressed air could propel shards of plastic throughout the area.


Expel all air from the pipeline during filling and again before testing for pressure or leaks. Automatic air-release valves are recommended. Compressed entrapped air can greatly amplify surges or pumping pressures. Also, compressed air might leak through a joint that will not leak water.




Scaled Product Drawing:




4-inch packaging




6-inch packaging





8-inch packaging



10-inch packaging



12-inch packaging



R&D Laboratory, Chemical Division

TEST REPORT

Compound: HT627 SBR Soft NSF
Product: C-900 Rieber, IPS (14-24")
Customer: Atkore
Date of issue: July 15 ,2025
Production month: June, 2025

Test Results

Physical and mechanical properties	Test method	Units	Specification ASTM F477HH	Results
Hardness	D2240	Shore A	50 to 60	53
Low Temperature Hardness after 22 h at -10 °C	D2240	Shore A	15 max	7
Tensile Strength	D412	MPa	13.8 min	17.0
Ultimate Elongation	D412	%	400 min	634
Compression Set 22 h at 70 °C	D395	%	20 max	15.1
Accelerated Aging 96 h at 70°C	D573	Points	8 max	2
Hardness Change		%	15 max	3.0
Tensile Change		%	20 max	-4.9
Elongation Change				
Water immersion 48 h at 70°C, Volume Change	D471	%	5 max	1.5
O ₃ Resistance 72 h at 40°C 50 pphm 20% Elong.	D1149	Appearance	No Cracks	No Cracks
PVC Compatibility 96 h at 70 °C	F477	Appearance	No marks,pits or blisters	No marks,pits or blisters

Note: NA

Name: Galina Potaskouev G.
Responsibility: R&D Manager: Chemical Division


ADDRESS
Pozos de Santa Ana, San José, Costa Rica

P.O Box
10903

PHONE
(506) 2205-1800

EMAIL
hultec@hultec.com

URL
hultec.com




SIZE	I.D.	W	T	X
4	117.20±0.61	27.91±0.63	13.00±0.41	8.4
6	169.16±0.76	32.11±0.63	15.00±0.41	9.6
8	223.29±0.79	36.40±1.80	17.02±0.46	10.9
10	274.70±0.89	43.84±0.80	20.02±0.41	14.9
12	325.95±0.99	48.75±0.80	22.07±0.51	15.8

MARKING:

SEE INDIVIDUAL DRAWING GASKET.

UNLESS OTHERWISE SPECIFIED, ALL DIMENSIONS ARE IN MILIMETERS

REV.	DESCRIPTION				APRVD.BY	DATE
SBR	55±5 shA	RMA A3	RMA F2	RMA 0.4 MM	—	—
MATERIAL	HARDNESS	TOLERANCES	FINISH	P.L. FLASH	Q.A.	PACKAGING
TECHNICAL SPECIFICATIONS ø4"—60" C900 SUPER RIEBER			PROJECT No.	DRAWN BY: WALTHER E.	DATE: MAY/12/22	SCALE: NONE
			—	CHECKED BY:	DATE:	CAD FILE: 1629-A22
 HULTEC + S&B TERRAMIX S.A			SUPERSEDES: —	No. 1629-A22		REV. 0 1 1



C900 Quality Assurance Program

Applicable Standards:

- AWWA C900: PVC Pressure Pipe and Fabricated Fittings
- FM1612: PVC Pipe and Fittings for Underground Fire Protection Service
- UL1285: PVC Pipe and Couplings and Oriented Pipe (PVCO) for Underground Fire Service

Overview: C900 quality is assured by:

- Conducting initial product qualification tests required by the standards and witnessed by independent 3rd-party certification agencies
- Routine dimensional checks during and after production
- Ongoing Plant QC physical tests required by the standards, and regularly audited by the certifying agencies

Initial Product Qualification (to AWWA C900 and UL1285)

- Certification tests performed by NSF included:
 - Sustained Pressure (1,000 hrs.)
 - Deflected Joint Pressure Performance
 - Extrusion Quality
 - Quick-Burst Pressure
 - Hydrotest
 - Flattening
 - Joint Assembly
 - Certification proving successful completion of these tests can be found at [Listing Category Search Page | NSF International](#)
- Certification tests performed by Factory Mutual (FM1612) included:
 - Deflected Joint Vacuum/Pressure Testing
 - Vacuum
 - Hydrostatic Strength Pressure (5 minutes)
 - One Hour Pressure
 - Quick-Burst Pressure
 - Pipe Stiffness
 - Pipe Impact
 - Certification proving successful completion of these tests and detailed Plant Audit can be found at _____

Production Checks

- Hourly checks (at a minimum) are performed and recorded for all dimensions in the Spec.
 - All dimensions are important, but some key areas we focus on are:
 - Consistent bell and lip lengths
 - Gaskets must be properly seated in the groove

- Wall thickness between min and max
- Bevel – required length and smooth all the way around. Rounded edge
- Insertion lines – as thin and crisp as possible, and properly located
- The print line is checked for accuracy of content, and legibility is monitored throughout the shift
- The spigot and bevel ends must be free of saw fuzz
- Workmanship - covers areas such as:
 - Smooth O.D. and I.D. and homogeneous throughout
 - No chips, blisters, visible cracks, holes, pits, foreign material, or other defects
 - No peeling, scaling, flaking, chalking, or crumbling
 - No drag lines or burns
 - Uniform as commercially practical in color, opacity, density, and other physical properties
- Secondary checks are made to verify dimensional integrity

Plant QC Tests

- Physical testing to C900, UL1285, and FM1612 requirements: Summary is as follows. NSF and FM conduct regular Plant audits to verify ongoing conformance to testing requirements, and successful performance

Test	Number of Samples		Test Frequency
	Start of Production	Routine QC	
Hydrotest (5 sec.) - every stick	Every stick during production		
Extrusion Quality	1 ring cut into segments - see ASTM D2152		Every 8 hrs.
Burst Pressure	5 - each must include a bell	1 - must include a bell	Every 24 hrs.
Flattening	3	1	Every 8 hrs.

DR	Pipe Pressure Class/Ratings, psi		Test Pressure, psi	
	C900 Pressure Rating	FM Pressure Rating	Hydrotest	Quick Burst
25	165		330	535
18	235	185	600	755
14	305	250	800	985

- Semi-annual sustained pressure testing is also performed, as required, to ensure ongoing compliance with standards and Agency requirements.

Submitted by:

Steven B. Gross, P.E.

Senior Quality Engineering Manager

PVC Pipe & Conduit

sgross@atkore.com



Date: 6/7/25

Shift: A

Operator: Ruxel


Line #: 1



W trailing digit = 12" wide pack
Enter Catalog P/N

Description	Catalog P/N	UPC Bar Code	Min	In. +/- tol	Max
CSGO DR18 8 x 20 GB	37800200	09111277627	6.250	0.50	7.250
Blue					

Overall Pipe Length, 20' +
Inches shown



3/2" Min. primitive no more than 5' apart
Atkore | Heritage Plastics 8" OOD DR18 PVC NSF-gw AHS/AWPA CS90-22 UL1285-22 PC 125 psi-T800 | FM Logo FM1612 PC 185 psi | PPC-FL Joint D x to Date, Time, Shift, Line x, UPC Barcode, Made in the U.S.A.

FM Logo - DR18
S. DR14 only

SPIGOT														
O.D., C			Wall Thickness, T1			15 deg. Bevel Length, F			Ref Line 1, E1			Ref Line 2, E2		
Nom		Out-of-Round				Nom		Nom		Nom				
9.05						0.750		6.250		7.250				
Min	+/- tol	Max	Min	Max	Max	Min	+/- tol	Max	Min	+/- tol	Max	Min	+/- tol	Max
9.035	0.015	9.065	0.503	0.563	0.050	0.625	0.125	0.875	6.125	0.125	6.375	7.125	0.125	7.375

BELL												
I.D.			Wall Thickness				DR		Bell Length, D			Up Length, G
Nom 9.100			Bell Lip				Behind Gasket		Nom 7.50			
Min	+/- tol	Max	Min	Max	Min	Max	≤	Min	+/- tol	Max	REF	
9.074	0.026	9.126	0.503	0.563	0.503	0.563	18	7.25	0.25	7.75	2.25	

Note 1: Thickening Length - REF (must cover entire bell and have minimal penetration into the spigot)

Note 2: Thickened Bell Wall - Approx. REF value. Actual thickening is whatever is required to hit the three key bell dimensions

Note 3: One-time measurement during production trials - does not need to be rechecked unless the process changes

9.5
0.655

INSPECTION DATA (Blue = Calculated Value)																	
SPIGOT										Bell							
PI-Type		Micrometer		Calipers		Steel Rule		Steel Rule		Calipers		Steel Rule		Micrometer		PI Tape	
Wall Thickness		OOR		Behind Gasket													
Min # of Measurements ->		8		6		4											
Time/Color Check	OD	Min	Max	Min OD	OOR = Max Minus Min	Max OD	Bevel	REF Line 1	REF Line 2	Bell I.D.	Bell Length	Up Length	Up Wall Thk.	Bell OD	Min. Thk.	DR = Bell OD/Thk.	
7 V	9.050	529	558	9.013	0.65	9.078	0.750	6.250	7.250	9.120	7.250	2.500	549	10.350	582	17.78	
8 V	9.050	529	558	9.013	0.65	9.078	0.750	6.250	7.250	9.120	7.250	2.500	540	10.350	582	17.78	
9 V	9.050	528	556	9.017	0.60	9.073	0.750	6.250	7.250	9.122	7.250	2.500	543	10.345	585	17.84	
10 V	9.050	528	556	9.017	0.60	9.073	0.750	6.250	7.250	9.122	7.250	2.500	543	10.345	583	17.78	
11 V	9.050	519	554	9.016	0.68	9.084	0.750	6.250	7.250	9.119	7.250	2.325	547	10.330	584	17.68	
12 V	9.050	519	554	9.016	0.68	9.084	0.750	6.250	7.250	9.119	7.250	2.325	547	10.530	584	17.68	
13 V	9.050	518	555	9.020	0.67	9.087	0.750	6.250	7.250	9.117	7.250	2.325	545	10.325	585	17.64	
14 V	9.050	518	555	9.020	0.67	9.087	0.750	6.250	7.250	9.117	7.250	2.325	545	10.325	585	17.64	
15 V	9.050	525	556	9.013	0.57	9.070	0.750	6.250	7.250	9.122	7.250	2.500	547	10.375	578	17.88	
16 V	9.050	525	556	9.013	0.57	9.070	0.750	6.250	7.250	9.122	7.250	2.500	547	10.335	579	17.88	
17 V	9.050	527	558	9.007	0.62	9.069	0.750	6.250	7.250	9.123	7.250	2.280	544	10.335	579	17.84	
18 V	9.050	527	558	9.007	0.62	9.069	0.750	6.250	7.250	9.123	7.250	2.280	544	10.335	579	17.84	

Check-mark in Time col. indicates acceptable color

QA TESTS

Number of Samples		Ex. - PS for GB				Ex. - PS for GB			
Test	Test Method	Start-Up	Routine QA	Test Freq. Every --	Production Hour	Indicate Start-Up (S) or Routine (R)	P/F	Production Hour	Indicate Start-Up (S) or Routine (R)
Quick Burst	TM-5a	5	1	24 hrs.	10:00	R	P	6:00	
Flattening	TM-6a	3	1	8 hrs.	10:00	R	P	6:00	R
Acetone Immersion	TM-12	1 ring cut into six (6) segments		8 hrs.	10:00	R	P	6:00	R

See Test Method for Conditioning and Test Details

A final test must be performed at the conclusion of production unless conclusion aligns with the every x-hour frequency

Rev D

PACKAGING AND WEIGHT

Top and Bottom Boards	46"
Side Boards	26"
Spacer Blocks	3-9/16"
Pieces per Row	5
No. of Pieces/Crate	10
No. of Rows/Crate	2
Footage/Crate	200
Target lbs./ft.	8.911
Crate Weight, lbs.	1782
Gasket Wt/Crate, lbs.	7.600

Compound	RLH20-J
NSF Compound Code	CPC-1



16100 South Lathrop Avenue
Harvey, IL 60426

Office 708-339-1610

Phone 800-882-5543

Web atkore.com

March 7, 2025

CERTIFICATE OF COMPLIANCE

This is to certify that AWWA C900 PVC Pipe manufactured by Atkore has been tested and evaluated in accordance with the standards and requirements set forth by NSF International. The product complies with the necessary health, safety, and performance standards established for NSF certification.

Product Type:

4" DR 14,18,25

6" DR 14,18,25

8" DR 14,18,25

10" DR 14,18,25

12" DR 14,18,25

NSF Standard: NSF/ANSI 14-2023: Plastics Piping System Components and Related Materials;
NSF/ANSI/CAN 61

Effective Date: 2/21/2025

Atkore ensures that the certified product is manufactured under strict quality control measures and meets all applicable regulatory requirements for safety and sanitation. Compliance with NSF standards reflects our commitment to providing high-quality and reliable products to our customers.

For verification of NSF certification, please visit the official NSF website at www.nsf.org/certified-products-systems

Best Regards,

Karol Szacilowski

Product Manager, HDPE and PVC

Atkore Plastic Pipe and Conduit

Mobile 708 603 5568

Email kszacilowski@atkore.com

Steven B. Gross, P.E.

Senior Quality Engineering Manager

Atkore Plastic Pipe and Conduit

Mobile 267 418 4264

Email sgross@atkore.com



Standards

AWWA C900 Pressure Pipe

Pipe Standards:

AWWA C900/ UL1285 / FM1612

Pipe Compound:

ASTM D1784; Cell Class 12454

Pipe Joint Standard:

ASTM D3139

Pipe Gasket Standard:

ASTM F477

Certifications:

NSF 14, NSF 61, FM1612



Disclaimers

Additions shall not be made to this document without prior evaluation and acceptance by NSF.
The below content does not represent the complete listings related to this product. For complete listing details, refer to the full listing details page for each product.

The following search criteria have been applied to generate the search results:
Product / Brand / Model / SKU / Trade Name / Company = **Atkore**

NSF/ANSI 14 Reclaimed Water - Pipe and Fittings

Show results by: **Products**

Trade Name	Product	Model/Size	Company	Product Type	Material Type	Product Standard
Heritage Plastics	10" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900
Heritage Plastics	12" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900
Heritage Plastics	4" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900
Heritage Plastics	6" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900
Heritage Plastics	8" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900



Disclaimers

Additions shall not be made to this document without prior evaluation and acceptance by NSF.
The below content does not represent the complete listings related to this product. For complete listing details, refer to the full listing details page for each product.

The following search criteria have been applied to generate the search results:
Product / Brand / Model / SKU / Trade Name / Company = **Atkore**

NSF/ANSI 14 Sewer Main - Pipe and Fittings

Show results by: **Products**

Trade Name	Product	Model/Size	Company	Product Type	Material Type	Product Standard
Heritage Plastics	10" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900
Heritage Plastics	12" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900
Heritage Plastics	4" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900
Heritage Plastics	6" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900
Heritage Plastics	8" DR 14, 18, 25	-	Atkore Plastic Pipe Corporation	Pipe	PVC	AWWA C900



Listing Details Heritage Plastics

Product Type	Pipe
Standard/Program	NSF/ANSI/CAN 61 - Drinking Water System Components - Health Effects
End Use	Pipes and Related Products
Trade Name	Heritage Plastics
Water Contact Temp	CLD 23
Water Contact Material	PVC
Company	Atkore Plastic Pipe Corporation 16100 South Lanthrop Avenue Harvey, Illinois, 60426 United States
Contact	708-225-2075

Listing Details by Facility

Size	Facility	Related Footnotes
>= 1/2"	Eugene, OR	[G] Product is Certified to NSF/ANSI/CAN 372 and conforms with the lead content requirements for "lead free" plumbing as defined by California, Vermont, Maryland, and Louisiana state laws and the U.S. Safe Drinking Water Act.
>= 1/2"	Tampa, FL	[G] Product is Certified to NSF/ANSI/CAN 372 and conforms with the lead content requirements for "lead free" plumbing as defined by California, Vermont, Maryland, and Louisiana state laws and the U.S. Safe Drinking Water Act.
>=1/2"	Dallas, TX	[G] Product is Certified to NSF/ANSI/CAN 372 and conforms with the lead content requirements for "lead free" plumbing as defined by California, Vermont, Maryland, and Louisiana state laws and the U.S. Safe Drinking Water Act.
>=1/2"	Louisville, KY	[G] Product is Certified to NSF/ANSI/CAN 372 and conforms with the lead content requirements for "lead free" plumbing as defined by California, Vermont, Maryland, and Louisiana state laws and the U.S. Safe Drinking Water Act.
>=1/2"	Pendleton, OR	[G] Product is Certified to NSF/ANSI/CAN 372 and conforms with the lead content requirements for "lead free" plumbing as defined by California, Vermont, Maryland, and Louisiana state laws and the U.S. Safe Drinking Water Act.

Disclaimers

The NSF Product Listings show currently listed companies and products. Although every reasonable effort has been made to assure accuracy, omissions or errors may occur due to the complexity of these listings and their conversion for the internet. If you notice an omission or error, please report it to NSF.

Additions shall not be made to this document without prior evaluation and acceptance by NSF.



Certificate of Compliance

This certificate is issued for the following:

Polyvinyl Chloride (PVC) Pipe and Fittings for Underground Fire Protection Service

AWWA C900 PVC pipe

Prepared for:

Atkore Plastic Pipe Corporation
16100 S Lathrop Ave
Harvey, Illinois 60426

Manufactured At:

Heritage Plastics South Inc (Atkore)
5128 W Hanna Ave
Tampa, FL 33634

Approval Standard: FM 1612 (October 2022)

Approval Identification: PR468007

Approval Granted: 22 November 2024

To verify the availability of the Approved product, please refer to www.approvalguide.com

Said Approval is subject to satisfactory field performance, continuing Surveillance Audits, and strict conformity to the constructions as shown in the Approval Guide, an online resource of FM Approvals.



David B. Fuller
VP, Manager – Fire Protection
FM Approvals
One Technology Way
Norwood, MA 02062





Certificate of Compliance

This certificate is issued for the following:

Polyvinyl Chloride (PVC) Pipe and Fittings for Underground Fire Protection Service

AWWA C900 PVC pipe

DR14 and DR18 in Sizes 4, 6, 8, 10 and 12 in.

Prepared for:

Atkore International
16100 S Lathrop Ave
Harvey, Illinois 60426
USA

Approval Standard: FM 1612 (October 2022)

Approval Identification: PR463080

Approval Granted: 26 September 2023

Approval Identification: PR467343

Approval Granted: 7 November 2023

To verify the availability of the Approved product, please refer to www.approvalguide.com

Said Approval is subject to satisfactory field performance, continuing Surveillance Audits, and strict conformity to the constructions as shown in the Approval Guide, an online resource of FM Approvals.



A handwritten signature in dark ink, appearing to read 'D.B. Fuller', is written over a horizontal line.

David B. Fuller
VP, Manager – Fire Protection
FM Approvals
1151 Boston-Providence Turnpike
Norwood, MA 02062





Production Facilities

Atkore-Heritage Plastics Manufactures PVC Gasketed and Solvent Weld Water Pipe at the locations listed below. For a plant tour, please reach out to the corresponding contact.

Plant Location	Contact
Tampa, Florida	Tom Lewis Water Pipe Sales Manager-Florida Email: tlewis@atkore.com Mobile: (757) 778-7518
Dallas, Texas	Karol Szacilowski Product Manager, HDPE and PVC Water Email: kszacilowski@atkore.com Mobile: (773) 558-1785
Louisville, Kentucky	Myra Hartong Water Pipe Sales Manager-Eastern Region Email: mhartong@atkore.com Mobile: (330) 575-6385
Eugene, Oregon	Tyler Kennedy Water Pipe Sales Manager-Western Region Email: tkennedy@atkore.com Mobile: (541) 206-0930
Pendelton, Oregon	Tyler Kennedy Water Pipe Sales Manager-Western Region Email: tkennedy@atkore.com Mobile: (541) 206-0930



Product Resolution Policy

Requirements and Guidelines

Document by: Steve Wasz
3/9/2021
Rev 7

Application

This policy applies to all orders placed with Atkore Inc. and any of its North American operating subsidiaries and facilities (collectively, “Atkore”), in conjunction with the Atkore standard warranty and other terms and conditions, available at Atkore.com/terms. Outlined in this policy are the requirements and procedures that must be followed to enable Atkore to address the following:

1. Claim Entry
2. Customer Return Requests: Request for Material Return based on Customer Error, Overstock or change in business need (“Customer Return”)
3. Customer Warranty, Quality or Nonconformance Complaints (“Customer Complaints”)

Exceptions:

1. Pricing errors are not entered in the SFDC system, and should be rectified directly with your designated CSR.
2. Damage that occurs in transit is NOT covered by Atkore, and claims should not be entered in SF. Pursuant to our standard terms and conditions, our products are shipped FOB or FCA (Incoterms), Atkore Facility, unless otherwise agreed to pursuant to written contract or in the case of retain orders. Title and Risk of Loss are transferred at the delivery point (our facility), and therefore any claims regarding damage in transit must be filed by the carrier directly by the customer.

I. Claim Entry - Salesforce.com

All customer claims will be entered using the Atkore CCS system in Salesforce.com (“SFDC”). Sales Agents will be required to hold a SFDC user license provided by the Atkore CRM Administrator prior to filing or pursuing any claims activity. Typically, a single license will cover all agents at the agent [company], and a common password will need to be shared. All claims will be worked through the customer’s sales representative (“CSR”), unless the claim relates to a “house account.” House accounts will be addressed by the applicable Inside Sales representative (ISR). The work instruction entitled: “CCS Training Guide” (available on the Agent portal) provides detailed steps necessary to enter a claim into the SFDC system. All required fields must be completed or system error messages will occur and prevent the case from being submitted. It is of crucial importance to select the correct Business Unit (“BU”) for the material that the customer is claiming. Each BU at Atkore has a specific and targeted Delegation of Approval (DOA) and failure to select the correct BU will result in the claim being rejected. The agent becomes the owner of the claim and has visibility to track status information as the complaint goes through the system. The agent is responsible to keep their customer up-to-date on all aspects of a complaint including seeing all claims are handled to closure.

While this Policy applies to all North American Atkore subsidiaries and facilities (excluding Unistrut Construction), the claims entry process through SFDC does not apply to the following product brands: Tectron, Calbond, Calbrite, US Tray, and Cii. Claims with those subsidiaries/facilities will be processed independently from the SFDC entry system. Please contact your Atkore CSR for questions regarding the proper claims process for these brands

II. Customer Return Requests

This section II governs the return of product due to “Customer Return Request,” defined as any material customer is seeking to return based on customer error, including but not limited to: customer entering the wrong part, overstock, or job changes.

A. Eligibility

- Stocking SKU’s only
- Made to Order Items are not returnable
- 100% of returned material must be in prime/sellable condition at Atkore’s sole discretion

- Metal Fittings and KoreFit products must be returned in full box/original packaging
- Material must be returned within 12 months (1 calendar year) of invoice date
- Material value must exceed \$100
- Restock fee is 25% of return value
- Freight is the responsibility of the customer

B. Condition of Product

- Clear photographs verifying the product and condition must be included when submitting the return request. Multiple views of the product are required to verify condition, and sufficiency of pictures will be at the discretion of Atkore. If pictures are not provided, the claim will be rejected. If further pictures are necessary to evaluate the product, the customer will be notified and will have 5 business days to provide added information or the claim will be closed.

C. Acceptance of Product and Credit Issuance

- All material credits are subject to review to determine if product(s) are sellable (prime) condition.
- 100% of return, must be deemed sellable (prime), or return will be rejected at customer's expense.
- If material is in prime condition, a credit will be issued for the lesser of (i) invoice value; or (ii) current market rate.

D. Unauthorized Returns / Rejected Returns / Non-Prime Returns

- Material returned in non-prime condition will be returned at customer's expense or scrapped at market value less negotiated handling cost.
- Atkore will provide written notice to customer of rejected, non-prime condition material
- Customer has 10 business days from the date of notice to resolve disposition of non-prime material

If customer fails to respond within 30 business days of the final notice, material will be scrapped. Customer will receive credit for the scrap value less Atkore's handling fee.

III. Warranty, Quality and Shipping Claims

This Section III governs the return of product under Atkore's express warranty(ies), or other acknowledged quality, shipping or nonconformance in Atkore's discretion.


A. General Requirements for Warranty/Quality Non-Conforming Material

- A claim must be entered in Sales Force.com and an RMA number assigned prior to sending material back to an Atkore or affiliated facility. Material that is returned without proper documentation will be refused at the gate and sent back at the customers expense.
- Verification of the non-conformance must be provided in the form of an agent physically inspecting product, sending pictures, returning product and/or sending samples. (Customer provided pictures can be used, but may not provide a true representation of the nature of the problem). Pictures are **required** and pictures / samples must be sent within ten (10) days of claim entry in SFDC. If required documentation is not received in that timeframe, the claim will automatically be closed, and notification will be sent to the reporting agent. Once a claim is closed, it cannot be resurrected in the system; a new claim would need to be generated and submitted.
- An explanation of the specifics of the non-conformance and resulting investigation must be described in the "Detailed Description of Claim" field. Note: This is a public description and will be printed on the paperwork accompanying the claim details. Please only report the facts in the detail.

- The bundle tag or carton labels, numbers and dates must be supplied and attached to the case file so those investigating may begin trace back. Some products have other distinguishing markers in the form of date codes or Plant codes that can aid in the investigation of defective material. Providing as much detail as possible is important if a trace back of material in the inventory is required and subsequent containment of product, if necessary.
- Invoice number and/or BOL number is required as part of complaint for tracking purposes.

B. Quality Complaint Requirements by Product Type

- **EMT/ IMC** – The date code must be reported. It is located as part of the logo of the product at the very end of the print line. Ex. AHK121461534 for Harvey product. Pictures and / or samples may be required depending on defect or severity.
- **Mechanical Products** – Depending on the customer requirements a date code may be available on product and should be specified in the detailed description. Pictures and / or samples may be required depending on defect or severity.
- **Cable Products** – Copies of the front and back of the tags or product label that is on the box from the material being claimed must be sent. If tags are not available, the assembly marker tape must be removed and photographed to identify the plant source. See example below for the number sequence required (listing number that begins with an E and has plant symbol in ():



- Photo of defect with the nonconformance clearly identified in the photo. For electrical issues a sample is required before acceptance of the claim.
- All quality claims must be returned in order to insure that defective material is not being used in the field and for quality to investigate the defect.
- Material returned must include the defect being claimed.
- Claims will be credited for the footage returned, not the footage purchased unless specified for specific jobs. In order to receive full credit, all material must be returned, or previous concession approved prior to return.
- Return is to be sent to the plant that manufactured the product and must be accompanied by RMA form. In certain cases, material may be sent to an alternate location to save cost.
- Any labor or additional material claims must be entered through the agent at the time of the PCR through Salesforce. Invoice for labor must be attached to the case file (subject to approval) in order for consideration.
- Part number, order#, length to be returned and length used must be included.
- **PPC Products**
 - Pictures of the print line are necessary including the PPC# and date / time stamp must be sent. Pictures and / or samples may be required depending on defect or severity.
- **Cable Management Products**
 - Pictures and / or samples are required depending on defect or severity.
 - Non-conforming material will need to be returned or scrapped in field based on QC evaluation at the time of claim entry.

C. Inspection and Containment of Atkore Warehouse Inventory

Atkore Quality Assurance (Q.A.) personnel will inspect the material at Atkore warehouse locations and contain in quarantine if necessary.

IV. Other Provisions

A. Validation/ Material Condition Verification Status Communication to Agent

If a claim for non-conforming material is found to be not valid or the material is returned due to a Customer Error in a non-saleable condition, the Customer will not be issued credit for the material at the discretion of the National Sales Director for each division.

B. Damaged Material Guidelines

- Damaged shipments should be accepted by the Customer and the items reported arriving damaged must have a driver-signed BOL copy noting the items rather than the whole load being refused. A copy of this document must be attached to the case file for review along with pictures of the load at time of delivery.
- Claims for damage must be entered within 10 business days of invoice.
- Pictures should be taken before the truck is unloaded and supplied upon submission to verify condition and determine if the material was damaged by the carrier or by the warehouse if it is deemed a considerable quantity.

C. Carrier Errors.

Damage that occurs in transit is NOT covered by Atkore Inc, and claims should **not** be entered in SF. Pursuant to our standard terms and conditions, our products are shipped FOB or FCA (Incoterms), Atkore Facility, unless otherwise agreed to pursuant to written contract or in the case of retain orders. Title and Risk of Loss are transferred at the delivery point (our facility), and therefore any claims regarding damage in transit must be filed by the carrier directly by the customer. The designated customer service representative can assist the Customer in filing by supplying necessary information to support the claim.

If the claim is related to a Retail or Government purchase order, or otherwise placed under delivery terms whereby Atkore retails title beyond our facility (e.g. DDP, FCA Delivery Point), Atkore will be responsible for filing such claims with the carrier. The invoice number and/or BOL number will be required as part of complaint for tracking purposes.

D. Short Shipments/ Wrong Material Guidelines

- Claims for shortages or wrong parts delivered must be entered into the system within 10 business days of invoice.
- Verification of the short shipment must be present either in the form of a Proof of Delivery (POD) signed short from the receiving warehouse and/ or a cycle count must be performed from the source location. Failing to provide this information can cause delays in issuing credit to the customer as the verification relies on cycle counting material at the plant/ warehouse.
- Concealed shortages must be in piece quantities only. Pallets with mixed material must be broken down and verification of the quantity/correct material performed upon arrival.
- Invoice number and/or BOL number will be required as part of complaint for tracking purposes.

1. **Acceptance, Complete Agreement.** All products or services furnished by any Atkore subsidiary (each a "Seller") to any buyer ("Buyer") are subject to these Terms and Conditions of Sale ("Terms"). Atkore is acting solely as billing agent for each Seller. These Terms and any accompanying quotation, confirmation of sale or invoice constitute the parties' entire agreement and may not be altered or modified except in a writing signed by each party, and supersede all prior or contemporaneous understandings, agreements, negotiations, representations and warranties, and communications, both written and oral. These Terms prevail over any of Buyer's general terms and conditions of purchase regardless whether or when Buyer has submitted its purchase order or such terms. Fulfillment of Buyer's order does not constitute acceptance of any of Buyer's terms and conditions and does not serve to modify or amend these Terms. Any different or additional terms or conditions furnished by Buyer are rejected and are not applicable to the sale or shipment of the products. In the event of conflict between Seller's quotation and these Terms, the former will govern. Notwithstanding anything herein to the contrary, if a written contract signed by both parties is in existence covering the sale of the Goods and Services covered hereby, the terms and conditions of said contract shall prevail to the extent they are inconsistent with these Terms. Trade custom, trade usage and past performance are superseded by these Terms and will not be used to interpret these Terms. Buyer's order will be binding on Seller only with regard to products shipped pursuant to Buyer's order or accepted in writing by Seller. Seller's failure to object to provisions contained in any purchase order, installation contract, or other communication from Buyer (including, without limitation, penalty clauses of any kind) will not be construed as a waiver of these conditions nor as an acceptance of any such provisions furnished by Buyer.

2. **Delivery and Title.** Delivery dates are estimates only and are not guaranteed. Time is not of the essence with respect to Seller's obligation to meet delivery requirements. Seller will use commercially reasonable efforts to make shipments as scheduled and may make partial shipments. All deliveries are Ex Works (Incoterms) shipping point and title to the products and risk of loss passes to Buyer on delivery to the carrier selected by Seller. Buyer agrees to accept the carrier of Seller's selection. Seller's shipment of the products is subject to Seller's approval of Buyer's credit rating. Seller may withhold shipment of products pending receipt of amounts due Seller or security for payment of amounts to become due to Seller as a result of the shipment of products. Products will be delivered in accordance with the tolerances and variations generally permitted in Seller's industry with respect to the quality of the products. A shipment will be deemed acceptable if the quantity of such shipment falls within 10% of the quantity specified, and the excess or deficiency will be charged or credited to Buyer proportionately. Seller reserves the right to ship in minimum quantities and standard packaging and to increase ordered quantities to such minimums.

3. **Inspection.** Buyer must inspect all shipments before unloading. If visible damage or shifting of the lading is detected in a rail shipment, Buyer must notify Seller in writing within 24 hours. If visible damage or shilling of the lading or shortages is detected in a motor carrier shipment, Buyer must note the damage or shortage on the carrier's copy of the delivery receipt and notify Seller in writing within 24 hours. If the damage or shortage is not ascertainable on arrival, Buyer must notify Seller in writing of any Nonconforming Goods within 10 days of receipt of shipment and furnishes such written evidence or other documentation as reasonably required by Seller. Failure to give such notice will constitute unqualified acceptance and a waiver of all such claims by Buyer against Seller. All claims for loss and damage in transit must be made by Buyer to the carrier. "Nonconforming Goods" means only the following: (i) product shipped is different than identified in Buyer's purchase order; or (ii) product's label or packaging incorrectly identifies its contents. If Buyer timely notifies Seller of any Nonconforming Goods, Seller shall, in its sole discretion, (i) replace such Nonconforming Goods with conforming Goods, or (ii) credit or refund the Price for such Nonconforming Goods, together with any reasonable shipping and handling expenses incurred by Buyer in connection therewith. Buyer shall ship, at its expense and risk of loss, the Nonconforming Goods to Seller's designated facility. If Seller exercises its option to replace Nonconforming Goods, Seller shall, after receiving Buyer's shipment of Nonconforming Goods, ship to Buyer, at Buyer's expense and risk of loss, the replaced Goods to the Delivery Point. Buyer acknowledges and agrees that the remedies set forth in this Section 3 are Buyer's exclusive remedies for the delivery of Nonconforming Goods. All sales of Goods to Buyer are made on a one-way basis and Buyer has no right to return Goods purchased under this Agreement without Seller's prior written approval.

4. **Prices and Taxes.** Buyer shall purchase the Goods from Seller at the prices set forth on the applicable quotation or as set forth in Seller's published price list in force as of the date Seller accepts Buyer's purchase order. All quotations will remain in effect for 5 calendar days unless sooner terminated by notice to Buyer. Prices quoted are subject to change without notice to Seller's prices in effect at the time of shipment; if the Prices should be increased by Seller before delivery of the Goods to a carrier for shipment, then these Terms shall be construed as if the increased prices were originally inserted herein, and Buyer shall be billed on the basis of such increased prices. All products may be combined in any proportion to meet weight requirements. All Prices are exclusive of all sales, use, and excise taxes, and any other similar taxes, duties, and charges of any kind imposed by any Governmental Authority on any amounts payable by Buyer. Buyer shall be responsible for all such charges, costs and taxes. Buyers with a valid state sales tax-exemption certificate must provide a copy of the certificate prior to payment, or taxes will be collected on purchases. If Buyer is purchasing from more than one Seller a separate tax exemption certificate is required for each.

5. **Payment.** Buyer shall pay all invoiced amounts due to Seller within 30 days from the date of Seller's invoice unless otherwise stated on Buyer's quotation or acknowledgment of purchase order. If credit has not been established Seller reserves the right to require payment, or the issuance of an irrevocable letter of credit, in advance of shipment. Buyer shall pay interest on all late payments at the lesser of the rate of 1.5% per month or the highest rate permissible under applicable law, calculated daily and compounded monthly. Buyer shall reimburse Seller for all costs incurred in collecting any late payments, including, without limitation, attorneys' fees. In addition to all other remedies available under these Terms or at law (which Seller does not waive by the exercise of any rights hereunder), Seller shall be entitled to suspend the delivery of any Goods or performance of any Services if Buyer fails to pay any amounts when due hereunder and such failure continues for 30 days following written notice thereof. Buyer shall not withhold payment of any amounts due and payable by reason of any set-off of any claim or dispute with Seller, whether relating to Seller's breach, bankruptcy or otherwise. If progress payments are required and are not paid when due, the entire contract price will become due and payable on demand or, at Seller's option, Seller may defer delivery or terminate the contract. If contract performance extends more than one calendar month, progress payments will be required and final payment will be made as designated by Seller. Seller reserves a purchase money security interest in each product shipped, which will be satisfied by payment in full. Seller has the right to file a copy of this document as a financing statement.

6. **Termination.** Buyer's order will be deemed a representation that Buyer is solvent and able to pay for the products ordered. If Buyer fails to make payments when due, if bankruptcy or insolvency proceedings are instituted by or against Buyer, if Buyer makes an assignment for the benefit of creditors, or if Buyer breaches any of these Terms, Buyer will be deemed to be in default and Seller will have the right to terminate its obligations by written notice without liability to Buyer or to any third party. Such termination will not affect Buyer's obligation to pay for products delivered and works in progress.

7. **Returns and Cancellation.** Seller reserves the right to discontinue the manufacture of; or change or modify the design and/or construction of, the products sold pursuant to these Terms without incurring any obligation to Buyer except a refund for monies previously paid for products that are discontinued or modified. No products may be returned without Seller's prior written approval, which may be withheld in Seller's sole discretion. If accepted, all products must be returned in saleable condition and Buyer must pay a handling charge, transportation charges and any costs incurred by Seller to place returned products in saleable condition (if not returned in saleable condition). Upon Seller's request, Buyer must return to Seller all products for which a refund is made. **Orders placed with and accepted by Seller may not be canceled or modified except upon Seller's written consent prior to shipment and Buyer's acceptance of Seller's cancellation and modification charges. Special or non-standard orders are not subject to cancellation or modification except on Seller's specified terms.**

8. **Warranties. (A)** Seller warrants to Buyer that for a period of 12 months from the date of shipment of the Goods ("Warranty Period"), that such Goods will materially conform to Seller's published specifications in effect as of the date of manufacture and will be free from material defects in material and workmanship. No warranty is given for products or components that have been (i) subject to misuse, improper installation, improper storage, corrosion, or negligence; (ii) disassembled, modified or repaired by unauthorized persons; or (iii) used in any manner contrary to Seller's instructions or recommendations. **SELLER DISCLAIMS ALL OTHER WARRANTIES, WHETHER EXPRESS OR IMPLIED BY LAW, COURSE OF DEALING, COURSE OF PERFORMANCE, USAGE OF TRADE, OR OTHERWISE, INCLUDING, WITHOUT LIMITATION, ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE, ANY WARRANTY THAT THE PRODUCTS WILL CONFORM TO ANY SAMPLES, ANY WARRANTY THAT THE PRODUCTS WILL NOT DISCOLOR OR THE TEXTURE OR FINISH WILL NOT CORRODE OR DETERIORATE, AND ANY WARRANTY REGARDING ANY ANCILLARY SERVICES RENDERED. (B)** Products manufactured by a third party ("Third Party Product") may constitute, contain, be contained in, incorporated into, attached to or packaged together with, the Goods. Third Party Products are not covered by the warranty in Section 8(A). For the avoidance of doubt, SELLER MAKES NO REPRESENTATIONS OR WARRANTIES WITH RESPECT TO ANY THIRD PARTY PRODUCT, INCLUDING ANY (i) WARRANTY OF MERCHANTABILITY; (ii) WARRANTY OF FITNESS FOR A PARTICULAR PURPOSE; (iii) WARRANTY OF TITLE; OR (iv) WARRANTY AGAINST INFRINGEMENT OF INTELLECTUAL PROPERTY RIGHTS OF A THIRD PARTY; WHETHER EXPRESS OR IMPLIED BY LAW, COURSE OF DEALING, COURSE OF PERFORMANCE, USAGE OF TRADE, OR OTHERWISE. **(C)** The Seller shall not be liable for a breach of the warranties set forth herein unless: (i) Buyer gives written notice of the defective Goods or Services, as the case may be, reasonably described, to Seller within 30 days of the time when Buyer discovers or ought to have discovered the defect; (ii) if applicable, Seller is given a reasonable opportunity after receiving the notice of breach of the warranty to examine such Goods and Buyer (if requested to do so by Seller) returns such Goods to Seller's place of business at Seller's cost for the

examination to take place there; and (iii) Seller reasonably verifies Buyer's claim that the Goods or Services are defective. Seller's liability will terminate upon expiration of the notice period. Seller's sole liability for non-conforming products will be to repair or replace the non-conforming product or return the purchase price paid therefore, at Seller's sole option. Buyer will bear all disassembly, shipment and reinstallation costs of repaired or replaced products. **THE REMEDIES SET FORTH HEREIN SHALL BE THE BUYER'S SOLE AND EXCLUSIVE REMEDY AND SELLER'S ENTIRE LIABILITY FOR ANY BREACH OF THE LIMITED WARRANTIES SET FORTH IN SECTION 8(A).**

9. **Limitation of Liability.** In no event shall Seller's aggregate liability arising out of or related to this agreement, whether arising out of or related to breach of contract, tort (including negligence), or otherwise, exceed the total of the amounts paid to seller for the goods sold hereunder. **IN NO EVENT SHALL SELLER BE LIABLE TO BUYER OR ANY THIRD PARTY FOR ANY LOSS OF USE, REVENUE OR PROFIT OR DIMINUTION IN VALUE, OR FOR ANY CONSEQUENTIAL, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR PUNITIVE DAMAGES WHETHER ARISING OUT OF BREACH OF CONTRACT, TORT (INCLUDING NEGLIGENCE), OR OTHERWISE, REGARDLESS OF WHETHER SUCH DAMAGES WERE FORESEEABLE AND WHETHER OR NOT SELLER HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES, AND NOTWITHSTANDING THE FAILURE OF ANY AGREED OR OTHER REMEDY OF ITS ESSENTIAL PURPOSE.**

10. **Indemnity.** Buyer agrees to indemnify, defend and hold harmless Seller, its agents, representatives, employees, officers, affiliates, successors, assigns and customers against any third party claim and damages arising out of: (a) patent infringement arising from compliance with Buyer's designs, specifications or instructions; (b) any injury (including death) to any person or damage to any property in connection with any act or omission of Buyer, its agents, employees, or subcontractors; and (c) any pollution, contamination, or other loss or damage to the environment or natural resources arising in connection with any products or services ordered by Buyer and provided by Seller, regardless of cause, including without limitation Seller's negligence, strict liability, or other act or omission and will pay all attorney's fees, costs and expenses of every nature incurred in such defense. Buyer agrees to maintain Worker's Compensation and Comprehensive General Liability insurance, including property damage coverage, as required by Seller and will provide insurance certificates upon request.

11. **Seller Drawings.** Any drawings submitted by Seller are only to show the general style, arrangement, and approximate dimensions of the products offered and no work will be based on drawings unless the drawings are certified. In no event will manufacturing or proprietary drawings be supplied.

12. **Compliance with Law.** Buyer shall comply with all applicable laws, regulations and ordinances. Buyer shall maintain in effect all the licenses, permissions, authorizations, consents, and permits that it needs to carry out its obligations under this Agreement. Buyer shall comply with all export and import laws of all countries involved in the sale of the Goods under this Agreement or any resale of the Goods by Buyer. Buyer assumes all responsibility for shipments of Goods requiring any government import clearance. If the products ordered will be exported from the United States, the quoted shipping dates are subject to receipt of all export documents and authorizations. Regardless of the ultimate destination, the prices quoted are based on packing for domestic shipment unless otherwise stated in writing. Buyer agrees to provide Seller in writing the ultimate destination and identity of the end-user prior to shipment if the products are to be exported. All products must be exported from the United States in accordance with applicable export laws and regulations. Seller may terminate this Agreement if any governmental authority imposes antidumping or countervailing duties or any other penalties on Goods. If the products are for resale or ultimate use by the U.S. Government, Seller shall comply with the applicable provisions of the Federal Acquisition Regulations pertaining to Equal Opportunity and Affirmative Action, Executive Order 11246 and any other applicable laws, rules and regulations.

13. **Waiver, Amendment and Modification.** No waiver by Seller of any of the provisions of this Agreement is effective unless explicitly set forth in writing and signed by Seller. No failure to exercise, or delay in exercising, any right, remedy, power or privilege arising from this Agreement operates, or may be construed, as a waiver thereof. No single or partial exercise of any right, remedy, power or privilege hereunder precludes any other or further exercise thereof or the exercise of any other right, remedy, power or privilege. These Terms may only be amended or modified in a writing stating specifically that it amends these Terms and is signed by an authorized representative of each party.

14. **Confidentiality.** Buyer agrees that all technical, business, financial and other confidential or proprietary information provided by Seller is confidential and may not be disclosed without Seller's prior written consent. Buyer (a) must use its best efforts (but in any event not less than those employed for safeguarding its own proprietary information, provided those efforts are reasonable) to keep such information confidential; (b) will not, except as specifically authorized in writing by Seller communicate the confidential information, or any knowledge that it is imparted through examining or working with such confidential information, to any third party or any employee, agent, or consultant of Buyer, unless such employee, agent, or consultant reasonably requires access to the confidential information and has undertaken an obligation to maintain its confidentiality; and (c) will not use the confidential information (i) to compete directly or indirectly with Seller; (ii) for its own account or purpose; (iii) to interfere with any actual and/or proposed business of Seller; or (iv) for any purpose other than the purchase of the products. Nothing in these Terms will restrict the use of information available to the general public.

15. **Force Majeure.** The Seller shall not be liable or responsible to Buyer, nor be deemed to have defaulted or breached this Agreement, for any failure or delay in fulfilling or performing any term of this Agreement when and to the extent such failure or delay is caused by or results from acts or circumstances beyond the reasonable control of Seller including, without limitation, acts of God, flood, fire, earthquake, explosion, governmental actions, war, invasion, or hostilities (whether war is declared or not), terrorist threats or acts, riot, or other civil unrest, national emergency, revolution, insurrection, epidemic, lockdowns, strikes or other labor disputes (whether or not relating to either party's workforce), or restraints or delays affecting carriers or inability or delay in obtaining supplies of adequate or suitable materials, materials or telecommunication breakdown or power outage. In the event of such delay, the completion date will be extended for a period equal to the time of such delay. Seller may terminate any contract without liability by written notice to Buyer if a delay in delivery or performance resulting from the foregoing events will continue for at least 60 days or if the manufacture or sale of goods is or becomes technically or economically impractical.

16. **Buyer's Acts or Omissions.** If Seller's performance of its obligations under this Agreement is prevented or delayed by any act or omission of Buyer or its agents, subcontractors, consultants, or employees, Seller shall not be deemed in breach of its obligations under this Agreement or otherwise liable for any costs, charges, or losses sustained or incurred by Buyer, in each case, to the extent arising directly or indirectly from such prevention or delay.

17. **Assignment.** Buyer shall not assign any of its rights or delegate any of its obligations under this Agreement without the prior written consent of Seller. Any purported assignment or delegation in violation of this Section is null and void. No assignment or delegation relieves Buyer of any of its obligations under this Agreement.

18. **Relationship of the Parties.** The relationship between the parties is that of independent contractors. Nothing contained in this Agreement shall be construed as creating any agency, partnership, joint venture or other form of joint enterprise, employment or fiduciary relationship between the parties, and neither party shall have authority to contract for or bind the other party in any manner whatsoever.

19. **Governing Law and Jurisdiction.** All matters arising out of or relating to this Agreement are governed by and construed in accordance with the internal laws of the State of Illinois without giving effect to any choice or conflict of law provision or rule that would cause the application of the laws of any jurisdiction other than those of the State of Illinois. Any legal suit, action, or proceeding arising out of or relating to this Agreement shall be instituted in the federal courts of the United States of America or the courts of the State of Illinois, and each party irrevocably submits to the exclusive jurisdiction of such courts in any such suit, action, or proceeding.

20. **Notices.** All notices, requests, consents, claims, demands, waivers, and other communications hereunder (each, a "Notice") shall be in writing and addressed to the parties at the addresses set forth on the face of the sales confirmation or to such other address that may be designated by the receiving party in writing. All Notices shall be delivered by personal delivery, nationally recognized overnight courier (with all fees pre-paid), facsimile (with confirmation of transmission), or certified or registered mail (in each case, return receipt requested, postage prepaid). Except as otherwise provided in this Agreement, a Notice is effective only (a) upon receipt of the receiving party, and (b) if the party giving the Notice has complied with the requirements of this Section.

21. **Severability.** If any term or provision of this Agreement is invalid, illegal, or unenforceable in any jurisdiction, such invalidity, illegality, or unenforceability shall not affect any other term or provision of this Agreement or invalidate or render unenforceable such term or provision in any other jurisdiction.





Training

PVC and HDPE Water Products

Please contact Karol Szacilowski for information regarding training, Training can also be provided by sales agents available in regional manufacturing facilities or local installations. Additionally, Atkore provides webinars with Uni-Bell for trainings about installing PVC pipe and other specific products.

Training Point of Contact:

Karol Szacilowski

Product Manager – HDPE and PVC Water Pipe Products

4949 Joseph Hardin Dr,

Email: kszacilowski@atkore.com

Mobile: (773) 558-1785